

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-033-20,678-0000

LEASE NAME Colter

WELL NUMBER 1-1

4950 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 1 TWP. 33 RGE. 19 (X) or (W)

COUNTY Comanche

Date Well Completed 6-28-85

Plugging Commenced 6-28-85

Plugging Completed 6-28-85

LEASE OPERATOR Bonray Energy Corporation

ADDRESS P. O. Box 20746, Oklahoma City, Oklahoma 73156

PHONE# (405) 848-6891 OPERATORS LICENSE NO. 9896

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6030

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	682	8 5/8"	6-14-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 135 sxs 60/40 poz, 6% gel as follows: 1350'-50 sxs; 690'-50 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; mousehole-10 sxs. Job by Sun Cementing. Plug down at 10:30 a.m. on June 28, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

STATE CORPORATION COMMISSION (Address) P. O. Box 329, Pratt, Kansas 67124

SUBSCRIBED AND SWORN TO before me this 9th day of July, 1985

NOTARY PUBLIC - State of Kansas  
MARY L. TJADEN  
My Appt. Exp. 3/22/88

Mary L. Tjaden  
Notary Public  
My Commission Expires: 3/22/88



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

**Oilfield Services, Inc.** 15-033-20678-0000

DRILLER'S WELL LOG

Colter #1-1  
 C N/2 NE NW Sec. 1-33S-19W  
 Comanche County, Kansas  
 Commenced: 6-13-85  
 Completed: 6-28-85  
 API #15-033-20,678  
 Operator: Bonray Energy Corporation

Depth		Formation	Remarks
From	To		
0	80	Conductor Pipe	Ran 16 joints (672') new, 24#,
80	540	Red Bed, Sand	8 5/8" surface casing. Set at
540	1018	Red Bed, Shale	682' with 300 sxs Lite, 1/4#
1018	1295	Red Bed	Floseal, 3% cc, 100 sxs Common,
1295	2060	Red Bed, Shale	1/4# Floseal, 2% cc. Cement did
2060	6030	Lime, Shale	circulate. Job by Sun Cementing.
		T.D.	Plug down at 11:30 a.m. on June
			14, 1985.

RTD 6030'


Plugged well with 135 sxs 60/40 poz  
 6% gel as follows: 1350'-50 sxs;  
 690'-50 sxs; 40'-10 sxs with solid  
 bridge; rathole-15 sxs; mousehole-  
 10 sxs. Job by Sun Cementing.  
 Plug down at 10:30 a.m. on June  
 28, 1985. State Plugger was out  
 of the Dodge City, Kansas Office.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Arnie Little*  
 ARNIE LITTLE, VICE-PRESIDENT



RECEIVED *Mary L. Tjaden*  
 STATE CORPORATION COMMISSION NOTARY PUBLIC

My Commission Expires:

5111 1 0 1985

*3/22/88*

7-10-85  
 CONSERVATION DIV.