

15-033-01009-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Commanche County, Sec. 11 Twp. 33S Rge. 17W (W)

Location as "NE/CNW%SW%" or footage from lines C of SW/4 of NW/4 of NW/4

Lease Owner J. M. Huber Corp.

Lease Name Einsel Well No. 1

Office Address Box 978, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-6-56 19

Application for plugging filed 2-6-56 19

Application for plugging approved 2-6-56 19

Plugging commenced 2-7-56 19

Plugging completed 2-7-56 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5970' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	300'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 300'. Set Halliburton Plug at 300' and cemented through the drill pipe with 35 sacks of cement.

Filled with mud to 20'; spotted plug with sack of hulls on top and cemented to surface with 15 sacks of cement. Top plug secured to surface with wire.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Moran Bros.
Address Oil & Gas Bldg., Wichita Falls, Texas

STATE OF KANSAS, COUNTY OF SEWARD, ss.
W.W. Henson (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.W. Henson
Box 978, Liberal, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10 day of February, 19 56

My commission expires 7-27-57 J. L. Kelly Notary Public.

PLUGGING
FILE SEC-11 T33 R17W
BOOK PAGE 37 LINE 12

2-11-56

DRILLER'S LOG
 15-033-01009-0000
 J. M. Huber Corporation

Einsel No. 1

SW NW NW Sec. 11-33S-17W
 Comanche County, Kansas

Formation	From	To
Red bed & shells	0	320
Red Bed	320	1046
Shale & Shells	1046	1723
Shale	1723	2369
Shale & lime	2369	2590
Lime & Shale	2590	2695
Shale & Lime	2695	3350
Shale	3350	3550
Lime & shale	3550	3613
Shale & lime	3613	3889
Shale	3889	4451
Shale & lime	4451	4580
Lime & shale streaks	4580	4631
Lime	4631	4865
Shale	4865	4982
Shale & lime	4982	4987
Lime	4987	5145
Shale & lime	5145	5316
Lime	5316	5394
Lime & shale	5394	5446
Lime	5446	5622
Lime & Chertq	5622	5695
Lime	5695	5750
Lime & shale	5750	5797
Lime	5797	5870
Sand & lime	5870	5950
Lime & Shale	5950	5970 TD - SLM

CERTIFIED TRUE & CORRECT

MORAN BROS., INC.

By:

T. E. Swift
 T. E. Swift

WITNESS:

Patsy Spencer

PLUGGING
 FILE SEC 11 T 33 R 17 W
 BOOK PAGE 37 LINE 12

COPY

RECEIVED
 COMMISSION
 123 1956
 2-23-56
 ON DIVISION