


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Comanche County. Sec. 8 Twp. 33S Rge. 20W ~~EXX~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C- NW NE SW
Lease Owner National Oil Company
Lease Name Maud Carpenter Well No. 1
Office Address Suite 550, 200 W. Douglas, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole
Date Well completed September 2, 1978
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced September 2, 1978
Plugging completed September 2, 1978
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5,205'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	565'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 5,205 ft. (rotary total depth) to 560 ft. Set plug at 560 ft. and cemented with 50 sacks. Filled hole with heavy rotary mud from 560 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4 $\frac{1}{2}$ inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing, Co., Inc.
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Signature of owner) ~~XXXXXXXXXXXXXXXXXXXX~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 78

My commission expires July 25, 1982

Elsie Willis RECEIVED
Notary Public.
STATE CORPORATION COMMISSION

SEP 11 1978

CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY National Oil Company

SEC. 8 T. 33S R. 20W
LOC. C-NW NE SW

FARM Maud Carpenter NO. 1

COUNTY Comanche

ROTARY TOTAL DEPTH 5,205'

COMM. August 21, 1978

COMP. September 2, 1978

CONTRACTOR H-30, Inc.

ISSUED September 8, 1978

CASING

10 3/4"

8 5/8" Set at 565' cemented w/800 sxs cement

ELEVATION 1,863 K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	770'
Sand, Shale and Red Bed	1,460'
Sand and Shale	1,968'
Lime and Shale	2,139'
Shale and Lime	3,205'
Lime and Shale	3,410'
Shale and Lime	3,770'
Lime and Shale	4,588'
Shale and Lime	4,676'
Lime and Shale	5,010'
Lime	5,120'
Lime and Shale	5,205'
Rotary Total Depth	5,205'


I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 8th day of September, 1978.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1978

CONSERVATION DIVISION
Wichita, Kansas