

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-191-20130-00-00

LEASE NAME Homestead (Lawson)

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER No. 4 (NW SE NE)

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

SEC. 2 TWP. 35S RGE. 2E (W) ~~(E)~~ ~~(N)~~ ~~(S)~~

COUNTY Sumner

Date Well Completed 1969

Plugging Commenced 7-21-88

Plugging Completed 7-27-88

LEASE OPERATOR A.C. Lawson

ADDRESS R.R. 1, Geuda Springs, Kansas 67051

PHONE# (316) 442-4358 OPERATORS LICENSE NO. 8200

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-21-88 (date)

by Glen Ward (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? \_\_\_\_\_

Producing Formation Bart Sand Depth to Top Appr. 3500 Bottom 3506 T.D. 3510

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8	176'	
Long String				5 1/2	3506	1850'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plug back to 3450 - Sand Gravel - Dump 5 sks cement - Shoot 1850' 5 1/2 pipe -  
Built plug 320' dump 20' rock - Bail dry - Readymix 6 yds - Well plugged  
1:00 P.M. 7-27-88

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wildcat Well Service, Inc. License No. 5496

Address 403 N. Hillcrest, Wichita, Kansas 67208

STATE OF KANSAS COUNTY OF COWLEY, ss.

A.C. LAWSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) A.C. Lawson

(Address) \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 19 88

AUG - 3 1988  
8-3-88  
CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires: 11-21-89

LaDonna G. Thompson  
Notary Public



CASING RECORD

8 5/8

176' Cemented  
w/120 sacks

5 1/2

3506' Cemented  
w/40 sacks

T. D.

3510'

KELLY BUSHING MEASUREMENT 5' ABOVE GROUND LEVEL.

FORMATION	DEPTH
Shale	0-55
Sand	65
Shale	130
Lime	176
Shale & Lime	200
Lime (broken)	555
Lime & Shale	990
Shale & Lime	1300
Lime & Shale	2150
Shale & Sand stks.	2460
Sand	2620
Shale	2802
Sand	2829
Sand & Shale	2903
Shale	3008
Lime	3257
Lime & Shale stks.	3340
Lime & Shale	3506
Sand	3510

TOPS

Layton	2802
Bartlesville	3506

Location: NW SE NE  
Section: 2-35S-2E  
Summer County, Kansas

Farm: Lawson #4

Well Owner: A. C. Lawson

Contractor: WHITE & ELLIS DRG., INC

Commenced: 5-5-69

Completed: 5-13-69

RECEIVED  
STATE CORPORATION COMMISSION

AUG - 3 1969

CONSERVATION DIVISION  
Wichita, Kansas