


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Comanche County, Sec. 2 Twp. 33S Rge. 17W (E) (W)
Location as "NE/CNW/SW" or footage from lines App. C SE NW
Lease Owner Pickrell Drilling Company
Lease Name Einsele "B" Well No. 1
Office Address 705 4th National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 16, 1969 19
Application for plugging filed May 16, 1969 19
Application for plugging approved May 16, 1969 19
Plugging commenced May 16, 1969 19
Plugging completed May 16, 1969 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 5200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13"	235' KB	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Heavy mud to 230'. Set plug. Cemented with
50 sacks cement. Heavy mud to 25'. Set plug.
Cemented with 30 sacks of cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas
05-26-1969

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) *C. W. Sebitts*
705 4th National Bank Bldg., Wichita, Kansas
(Address)



My commission expires May 10, 1970
L. M. Whiting Notary Public

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas 67202
LOCATION: Einsel "B" No. 1
App. C SE NW Sec. 2-33S-17W
Comanche County, Kansas
CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

Rotary Drilling Commenced 4/29/69
Rotary Drilling Completed 5/16/69

CASING RECORD: Ran 13 jts. 13" casing set @ 235' KB. Cemented with 225 sacks common cement. Circulated. Completed 10:00 PM, April 29, 1969. No oil string run. D & A plugged May 16, 1969.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

45	Sandy Clay	C. F. S.
260	Red Rock	5158
915	Red Beds & Shale	5170
1300	Shale & Shells	5200
1820	Shale	
2110	Shale & Shells	
2200	Shale w/ Lime	
2390	Lime & Shale	
2990	Lime	Slope Tests
3008	Shale & Lime	2000
3095	Lime & Shale	2500
3265	Shale & Lime	3000
3348	Lime & Shale	3500
3585	Shale & Lime	4000
4095	Lime & Shale	4500
4210	Shale & Lime	5000
4247	Shale	
4450	Shale w/ Lime	
5140	Lime	
5158	Mississippian	S. L. M.
5170	Lime	Board 4512.66
5185	Mississippian	Strap 4508.18
5200	Lime RTD	4.48 Short
5201	LTD	

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas
05-26-1969

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SELEWICK } ss.:

On this 24th day of May, 1969, before me the undersigned, a Notary Public, in and for the County of Selewick, Kansas, the undersigned, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.
Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
L. M. Whiting Notary Public