

15-833-20060-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Comanche County, Sec. 3 Twp. 34 Rge. (E) 16 (W)
Location as "NE/CNWxSWx" or footage from lines NW/NW
Lease Owner Shenandoah Oil Corporation
Lease Name Merrill Ranch Well No. C-3
Office Address 1500 Commerce Bldg, Ft. Worth, Texas 76102
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 17 1970
Application for plugging filed January 20 1970
Application for plugging approved January 19 1970
Plugging commenced January 16 1970
Plugging completed 4:30a.m. January 17 1970
Reason for abandonment of well or producing formation non-commercial

NORTH

X			

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production -- 19--
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation Mississippi Depth to top 4854' Bottom 5057' Total Depth of Well 5057' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	tight	4854'	5057'	8 5/8"	532'	none

RECEIVED
STATE CORPORATION COMMISSION
1-22-70
JAN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from -- feet to
-- feet for each plug set.

Hole filled with heavy mud. Spotted 25 sacks cement @ 532 feet, spotted
10 sacks cement plug from 0' - 30'. Welded steel plate on top of 8 5/8" surf.
casing.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bowers Drilling Co.
Address Wichita, Kansas

STATE OF Texas COUNTY OF Tarrant, ss.
Harold E. Burke (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold E. Burke
1500 Commerce Bldg., Ft. Worth, Texas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of January, 1970

Connie L. Bulmer

My commission expires 6-1-71

Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1970
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG
Merrill Ranch C #3
NW NW S3-T34N-R16W
Comanche County, Kansas
Elevation: 1656' KB

<u>FROM:</u>	<u>TO:</u>	<u>CONTENT:</u>
0'	293'	Sand & shale
293'	535'	Red Bed
535'	1671'	Lime & shale
1671'	2313'	Lime & shale
2313'	2920'	Lime & shale
2920'	3505'	Lime & shale
3505'	4037'	Lime & shale
4037'	4216'	Shale & lime
4216'	4435'	Lime & shale
4435'	4703'	Lime & shale
4703'	4896'	Lime & shale
4896'	5015'	Lime
5015'	5050'	Lime
5050'		Total Depth

STATE OF TEXAS
COUNTY OF TARRANT

Harold E. Burke, Vice President of Shenandoah Oil Corporation, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Harold E. Burke
Harold E. Burke

Subscribed and sworn before me this 27th day of January, 1970.

Connie L. Beckman
Notary Public, Tarrant County

My commission expires 6-1-71.