

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21536-00-00
Spot: SWSSEWNE Sec/Twnshp/Rge: 15-24S-15W
4010 feet from S Section Line, 1685 feet from E Section Line
Lease Name: CUMMINS Well #: 4-15
County: STAFFORD Total Vertical Depth: 4550 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4374	1850	WITH 275 SX CMT
SURF	8.625	263		WITH 210 SX CMT

Well Type: SWD UIC Docket No: D21833.0 Date/Time to Plug: 04/30/2014 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4320' & 5 SX CMT. PLUG AT 1020' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2014 11:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

SANDED TO 4300' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1030' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 41' WITH 20 SX CMT. TOPPED OFF WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA

MAY 06 2014

RECEIVED

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

MAY - 1 2014

KCC DODGE CITY

Form CP-2/3

RL