

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25120-00-00  
Spot: SWNENESW Sec/Twnshp/Rge: 7-20S-13W  
2080 feet from S Section Line, 2000 feet from W Section Line  
Lease Name: NICOLET 'A' Well #: 1-7  
County: BARTON Total Vertical Depth: 3675 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3675		135 SX
SURF	8.625	797		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/02/2014 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: FG HOLL Phone: (620) 793-0915

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/02/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

05/01/2014-Sanded back to 3120' and spotted 5 sx cement on top.  
05/02/2014- Cut casing at 1900'. Pulled casing to 1650' and pumped 140 sx cement w/200 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 700' and pumped 50 sx cement w/100 # hulls. Pulled casing to 450' and pumped 105 sx cement w/100 # hulls. Cement circulated and filled cellar. POOH and cellar stayed full.

GPS: 38.32463 -098.80419

Perfs:

Top	Bot	Thru	Comments
3560	3563		
3539	3547		
3521	3528		
3502	3506		
3382	3386		
3301	3307		
3280	3284		

Remarks: QUALITY WELL SERVICE TICKET # 31925

Plugged through: CSG

KCC WICHITA

MAY 15 2014

RECEIVED

District: 04

Signed Ray A Dinkel  
6/04/14 (TECHNICIAN)

CM