

1 030457

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,678-0000
NE NW, SEC. 1, T 33 S, R 19 W/X
4950 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9896

Lease Name Colter Well # 1-1
County Comanche 195.98
(Simpson)
Well Total Depth 6030 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 682

Operator: Bonray Energy Corporation
Name & Address 2644 NW 63rd
Oklahoma City, OK 73156

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149
Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 9:00 am Day: 28 Month: June Year: 19 85

Plugging proposal received from Tom Harmon
(company name) Wheatstate (phone) 316-672-7514
Elevation 2040'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1350

1st plug at 1350' with 50 sx cement

2nd plug at 690' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:30 am Day: 28 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1350' with 50 sx cement, 2nd plug at 690' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
7-1-85
JUL 01 1985

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan # 283512
(If additional description is necessary, use BACK of this form.)
Conservation Division
Wichita, Kansas

INVOICED

DATE 7-12-85

INV. NO. 8887

Signed Steve Durrant
(TECHNICIAN)