

7-12

To: 120274
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,484-A-0001

SE NW NE, SEC. 2, T 24 S, R 13 W/E
4290 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4419

Lease Name Heyen Well # 1

Operator: Bear Petroleum

County Stafford 131.63

Name & Address Box 243

Well Total Depth 4050 feet

Derby, KS 67037

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 12 Month: 7 Year: 1989

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4032' PBD 3890' Perfs at 3821-30'

1st plug sand back to 3770' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 p.m. Day: 12 Month: 7 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3770' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-400 psi and shut in 275 psi.

RECEIVED STATE CORPORATION COMMISSION

JUL 19 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1580' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED

observe this plugging.

DATE 7-20-89

Signed Duane Rankin (TECHNICIAN)

INV. NO. 25377