

RCVD
KCC

1 090343

06-09-14

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,898
SE NW, SEC. 19, T. 33 S, R. 20 W X
1980 feet from N S section 11n
3300 feet from E section 11n

TECHNICIAN'S PLUGGING REPORT
Operator License # 30444

Lease Name Forster Well # 1
County Comanche
Well Total Depth 6735 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 663

Operator: Charter Production Co.
Name
Address 224 E. Douglas, Ste. 400
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling Inc. License Number 5380

Address 110 N. Market, Ste. 411, Wichita, KS 67202

Company to plug at: Hour: 9:30 a.m. Day: 19 Month: 10 Year: 1993

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling, Inc. (phone) 316-265-1072

to fill hole with heavy mud and spot cement through drill pipe Anhydrite 835'

1st plug at 835' with 30 sx cement, 2nd plug at 690' with 50 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 a.m. Day: 19 Month: 10 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 835' with 30 sx cement,

2nd plug at 690' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

1 (XXX / did not) observe this plugging.

Signed (TECHNICIAN)