

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1 040056

2-19-88

144

API NUMBER 15-N/A 15-033-20213-00-00 R

C NE/4, SEC. 7, T 33 S, R 20 W 1/4
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Hinkhouse Well # A-1

Operator: W.L. Kirkman, Inc.

County Comanche 172.58

Name & Address P.O. Box 782290

Well Total Depth 5310 feet

Wichita, KS 67218-2290

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 544

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 p.m. Day: 19 Month: 2 Year: 19 88

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 5309' Perfs at 5219-21' Elevation 1898'GL

1st plug sand back to 5160' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 19 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 5160' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 350 psi and shut in 50 psi.

STATE CORPORATION COMMISSION PCVD
FEB 24 1988 022488

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If applicable) observe this plugging.

DATE 2-29-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 19933