

To: 1 090235  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-20

API NUMBER 15- 033-20,865-DD-00/171 R

E/2 SW SW, SEC. 5, T. 33 S, R. 20 W/4E  
4620 feet from NY section line  
990 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444  
Operator: Charter Production Company  
Name & Address: 224 E. Douglas, Ste. 400  
Wichita, KS 67202

Lease Name John Herd Well # 1  
County Comanche 175.50  
Well Total Depth 5400 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 537

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address P.O. Box 12383, Wichita, KS 67277-2383

Company to plug at: Hour: 2:15 a.m. Day: 20 Month: 11 Year: 19 92

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling, Inc. (phone) 316-945-9935

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 920'  
1st plug at 930' with 50 sx cement, 2nd plug at 570' with 50 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 4:30 a.m. Day: 20 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 930' with 50 sx cement,  
2nd plug at 570' with 50 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

RECEIVED

NOV 24 1992

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(if additional description is necessary, use BACK of this form.)

I (agent) did not observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE DEC 10 1992  
INV. NO. 37050

EFFECTIVE DATE: 11-5-92

DISTRICT # 1  
SEA7? Yes  No

State of Kansas 15-033-20865-0000 FORM MUST BE TYPED  
NOTICE OF INTENTION TO DRILL FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 11 7 92  
month day year

Spot East  
E 2 SW SW Sec 5 Twp 33 S. Rg 20  West

OPERATOR: License # 30444  
Name: Charter Production Company  
Address: 224 E. Douglas Suite 400  
City/State/Zip: Wichita, KS 67202  
Contact Person: Jerald W. Rains  
Phone: (316) 264-2808

4620 feet from South North line of Section  
990 feet from East West line of Section  
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Comanche  
Lease Name: John Herd Well # 1  
Field Name: Wildcat Overacker

CONTRACTOR: License # 5380  
Name: Eagle Drilling, Inc.

Is this a Prorated/Spaced Field? no yes   
Target Formation(s): Morrow, Miss  
Nearest Lease or unit boundary: 990'  
Ground Surface Elevation: 1883 feet MSL

Well Drilled For: Well Class: Type Equipment:  
 Oil  Enh Rec  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 OUVO  Disposal  Wildcat  Cable  
 Seismic:  # of Holes  Other

Water well within one-quarter mile:  yes  no  
Public water supply well within one mile:  yes  no  
Depth to bottom of fresh water: 90'  
Depth to bottom of usable water: 90' 180'

If OUVO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Surface Pipe by Alternate:  1  2  
Length of Surface Pipe Planned to be set: 525'  
Length of Conductor pipe required: \_\_\_\_\_  
Projected Total Depth: 5300'  
Formation at Total Depth: Miss

Directional, Deviated or Horizontal wellbore?  yes  no  
If yes, true vertical depth: \_\_\_\_\_  
Bottom Hole Location: \_\_\_\_\_

Water Source for Drilling Operations: \_\_\_\_\_ well \_\_\_\_\_ farm pond \_\_\_\_\_ other  
DNR Permit #: \_\_\_\_\_  
Will Cores Be Taken?  yes  no  
If yes, proposed zone: \_\_\_\_\_

Expires 4-5-93 AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Batch  
SPUD DATE 11-09-92 INIT. GB  
LENGTH SURFACE PLANNED 525  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 5/8 @ 537 CONDUCTOR  
ANHYDRITE T- 1 B- 920 ELEVATION  
TD 5400 FORMATION \_\_\_\_\_  
RAN PIPE @ SX DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
\_\_\_\_\_ SX \_\_\_\_\_ Y \_\_\_\_\_ N \_\_\_\_\_  
\_\_\_\_\_ Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
\_\_\_\_\_ Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
\_\_\_\_\_ Anhydrite Base @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
\_\_\_\_\_ 1/2 Base Anyh. @ 930 Ft. W/ 50 SX  
\_\_\_\_\_ 1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
\_\_\_\_\_ Bottom Surface @ 570 Ft. W/ 50 SX  
\_\_\_\_\_ 40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 13 SX MOUSE HOLE W/10 SX  
WATER WELL 40 SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
TECHNICIAN SJA DATE 11-19-92 Hauling \_\_\_\_\_  
TYPE OF CEMENT 60/40 1870  
STARTING TIME 2:15 (AM/PM) DATE 11-20-92  
COMPLETION TIME NOV 20 (AM/PM) DATE 11-20-92  
CEMENT COMPANY Halliburton