

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20235-00-00
Spot: SENE Sec/Twnshp/Rge: 2-32S-28W
4428 feet from S Section Line, 378 feet from E Section Line
Lease Name: KOBS Well #: 1
County: MEADE Total Vertical Depth: 5508 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5414	1700	WITH 275 SX CMT
SURF	8.625	1360		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/30/2014 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 150# HULLS & 20 SX CMT AT 5320'. PLUG AT 1390' WITH 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS Witness Type: PARTIAL
Date/Time Plugging Completed: 05/30/2014 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 150# HULLS & 20 SX CMT AT 5320'. PRESSURED TO 500#. LOADED HOLE WITH MUD. 1ST PLUG AT 1390' WITH 50 SX CMT. 2ND PLUG AT 450' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CMT CIRCULATED & HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5320	5324		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

JUN 06 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed [Signature]
✓ 6/10/14 (TECHNICIAN)

RECEIVED
JUN - 4 2014
KCC DODGE CITY

[Signature]
Form CP-2/3