

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21252-00-00
Spot: NWNESENW Sec/Twnshp/Rge: 20-28S-4E
3710 feet from S Section Line, 3077 feet from E Section Line
Lease Name: KEYSA Well #: 1
County: BUTLER Total Vertical Depth: 2491 feet

Operator License No.: 31389
Op Name: NOBLE PETROLEUM, INC.
Address: 3101 N ROCK RD STE 125
WICHITA, KS 67226

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 2488 | | 60 SX |
| SURF | 8.625 | 200 | | 80 SX |

Handwritten notes:
CP-4/CP-1
in RECORDS
WCC
3/27/14

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2014 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: MIKE KISER Company: HIZEY SERVICE & SUPPLY Phone: (316) 775-5496

Proposed Plugging Method: AS PER KCC RULES & REGS / CEMENT 50' ABOVE PERF @ 2400', 250' -0' CIRC.

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL
Date/Time Plugging Completed: 03/17/2014 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2460', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL, 3% CC, 3/4# POLY FLAKE & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2141'. RIH W/TBG @ 250', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION. MIXED & PUMPED 101 SXS 60/40 POZMIX 4% GEL, CEMENT DID NOT CIRCULATE. SDON. 3-17-2014, TAGGED CEMENT TOP @ 391'. RIH W/TBG @ 297', CONSOLIDATED MIXED & PUMPED 38 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED WELL BACK TO SURFACE W/12 SXS. CONSOLIDATED CEMENT TICKET #42931, & 42934.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2456 | 2465 | CSG | |

KCC WICHITA

Remarks: CEMENT @ SURFACE ON BACKSIDE OF CASING/ COMPLIANCE/DENIED TA

APR 28 2014

Plugged through: TBG

RECEIVED

District: 02

Signed

Handwritten signature: Duane Krueger
6/29/14 (TECHNICIAN)

Handwritten mark: ✓