

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20990-00-01  
Spot: NENESW Sec/Twnshp/Rge: 19-12S-21W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SHERFICK A Well #: 2  
County: TREGO Total Vertical Depth: 4003 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4002		200 SX
SURF	8.625	217		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2014 9:30 AM  
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC  
Proposal Rcvd. from: THOMAS ATKINS Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 623-8120

Proposed Plugging Method: Tubing stuck in hole at 2214'.  
Rods stuck in hole at 2040'. Can not get any more out of hole.  
Perforations at 3721' - 3724', 3741' - 3747', 3912' - 3936', 3994' - 3999'.  
Shot perforations at 212', 950' and 1727'.  
Orderd 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2014 12:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1995' and pumped 240 sx cement w/300 # hulls. Good circulation of cement.  
Pulled tubing out. Casing full from back side squeeze. Tied on to back side and squeezed with  
60 sx cement. Hole standing full.

GPS: 38.99348 -099.69743

Perfs:


Top	Bot	Thru	Comments
3994	3999		
3912	3936		
3741	3747		
3721	3724		
3453	3456		

Remarks: ALLIED CEMENT TICKET #55236

Plugged through: TBG

District: 04

Signed

  
6/10/14  
(TECHNICIAN)

CM

KCC WICHITA

MAY 15 2014

RECEIVED

MAY 08 2014

Form CP-2/3