

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-22566-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 1-29S-9E
350 feet from N Section Line, 1670 feet from E Section Line
Lease Name: JORDAN Well #: 2-1
County: ELK Total Vertical Depth: 2585 feet

Operator License No.: 34779
Op Name: LR ENERGY, INC.
Address: 8150 N. CENTRAL EXPY, STE 1605
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2577		405 SX
SURF	8.625	40		55 SX
T1	2.875	2577		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2013 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JACOB MCCLAIN Company: _____ Phone: (620) 627-2499

Proposed Plugging Method: 50' cement plug on bottom. Pump gel spacer to 2482'. Pump 100' plug over perforations. Pump gel spacer to 1460'. Pump 50' plug over KC Lime. Pump gel spacer to 500'. Pump from 500' to surface with cement.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 11/27/2013 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Squeezed well with 245 sacks of 60/40 pozmix down casing. Well was shut in with pressure. Let well set than topped well off.

Perfs:

Top	Bot	Thru	Comments
2427	2482		
RECEIVED MAY 13 2014 KCC Chanute Dist. #3 DS			

Remarks:

Plugged through: CSG

District: 03

Signed [Signature]
6/09/14 RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

MAY 19 2014

CONSERVATION DIVISION
WICHITA, KS