

2 050755

7-27-88

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-191-20130-00-00

NWSENE, SEC. 02, T 35 S, R 02 WE

4150 feet from N/S section line

470 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8200

Lease Name Lawson Well # 4

Operator: A.L. Lawson

County Sumner 114.08

Name & Address R.R. 1

Well Total Depth 3510 feet

Geuda Springs, KS 67051

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 176

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Wildcat Drlg. License Number

Address

Company to plug at: Hour: Day: Month: 7 Year: 19 88

Plugging proposal received from

(company name) (phone)

were: 5 1/2" casing set at 3506 w/40 sx. Open hole to 3510. Sand back to 3450 and dump 5 sx. cement. Shoot and pull casing. Redimix from 300 to surface.

Plugging Proposal Received by Glenn Ward (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:00 p.m. Day: 27 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT Sand and gravel back to 3450 and dumped 5 sx. cement w/dump bailer.

Shot and pulled 1900 feet of casing. Built rock bridge from 325 to 302 and filled to surface w/Redimix.

Remarks: Ark City Concrete Co.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 8-9-88

Signed Glenn Ward (TECHNICIAN)

INV. NO. 21823 SEP 12 1988

RECEIVED STATE CORPORATION COMMISSION AUG 5 1988 CONSERVATION DIVISION Wichita, Kansas