

1061133

15-033 - 30068-00-00

API NUMBER 15- Drill Completion Date 4/13/66

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE NW, SEC. 1, T 33 S, R 17 W/EX

4290 feet from S section line

3630 feet from E section line

Lease Name Gregg "A" Well # 1-1

County Comanche 168.45

Well Total Depth 5183 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 409

TECHNICIAN'S PLUGGING REPORT

Operator License # 3351

Operator: PetroCorp
Name & Address: 300 North Atrium
16800 Greenspoint Park Drive
Houston, TX 77060

Abandoned Oil Well _____ Gas Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Pratt Well Service License Number 5893

Address: Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:45 p.m. Day: _____ Month: 8 Year: 19 88

Plugging proposal received from Preston Izard

(company name) PetroCorp (phone) 713-875-2500

were: 4 1/2" at 5182' PBD 5174' Perfs at 5142-68'

1st plug set CIBP at 4650' and dump 4 sx common cement on top,

2nd plug pump 65 sx cement at 1000', 3rd plug pump 60 sx cement at 430',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 24 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4650' and dumped 4 sx common cement on top.

2nd plug pumped 65 sx cement at 1000',

3rd plug pumped 60 sx cement at 430',

4th plug pumped 10 sx cement at 40',

2nd, 3rd, and 4th plug pumped through tubing.

Richard Lacey witnessed 1st plug set and Paul Luthi saw top three plugs set.

Remarks: Used Class A cement by Dowell. Recovered 1000' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (old XXXXXX) observe this plugging.

DATE 8-29-88

INV. NO. 22050

8-24

Signed Paul A. Luthi (TECHNICIAN)