

To: 1 090291 6-3  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,460-00-01

C NW SE, SEC. 3, T. 33 S, R. 17 W/EK  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5278

Lease Name Victor 3 Well # 2 Re-entry

Operator: Enron Oil & Gas Company

County Comanche

Name & Address 20 N. Broadway, Ste. 830

Well Total Depth 5150 167.37 feet

Oklahoma City, OK 73102

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 453

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Brandt Drilling Company, Inc. License Number 5840

Address 200 W. Douglas, Ste. 700, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 3 Month: 6 Year: 19 93

Plugging proposal received from Sam Hummel

(company name) Enron Oil & Gas Co. (phone) 405-239-7800

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 900' with 50' sx cement, 2nd plug at 470' with 50' sx cement,

3rd plug at 40' with 10' sx cement,

4th plug to circulate rathole with 15' sx cement,

5th plug to circulate mousehole with 10' sx cement.

Plugging Proposal Received by Steve Middleton

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:30 p.m. Day: 3 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 900' with 50' sx cement,

2nd plug at 470' with 50' sx cement,

3rd plug at 40' with 10' sx cement,

4th plug to circulate rathole with 15' sx cement,

5th plug to circulate mousehole with 10' sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Western Cementing.

(If additional description is necessary, use BACK of this form.)

did not observe this plugging.

DATE 6-22-93

INV. NO. 37974

Signed \_\_\_\_\_  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 6 1993  
CONSERVATION DIVISION  
Wichita Kansas

06-08-1993