

1 090064

15-033-20111-0000 4-17-90

152 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
201 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 1/22/72

W/2 NE NW, SEC. 4, T 34 S, R 16 W/EX

4620 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8222

Lease Name Merrill Well # 1

Operator: Buttonwood Petroleum, Inc.

County Comanche 164.13

Name & Address 9 East 4th Street, #605

Well Total Depth 5050 feet

Tulsa, OK 74103

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 525

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Proctor Casing Pullers, Inc. License Number 6418

Address 6209 Aluma Valley Drive, Oklahoma City, OK 73121

Company to plug at: Hour: 8 a.m. Day: 17 Month: 4 Year: 19 90

Plugging proposal received from Larry Murray

(company name) Proctor, Casing Pullers, Inc. (phone) 405-478-0591

were: 4 1/2" at 5049' PBSD 5015' Perfs at 4892-4921'

1st plug pump 25 sx cement at 4800',

2nd plug pump 40 sx cement at 700',

3rd plug pump 50 sx cement at 550',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:15 p.m. Day: 17 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 50 lbs. hulls and 25 sx cement at 4500' (maximum pressure 2000 psi),

2nd plug pumped 40 sx cement at 700',

3rd plug pumped 50 sx cement at 550',

4th plug pumped 10 sx cement at 40'.

Remarks: Used Class H cement by Proctor, Casing Pullers. Recovered 3210' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-3-90

INV. NO. 28015

RECEIVED APR 23 1990 CONSERVATION DIVISION Wichita, Kansas

Signed Michael R Wilson (TECHNICIAN)