

To? 1 040427
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-11
API NUMBER 15- 033-20,784-0000
SW SW NE, SEC. 1, T 34 S, R 16 W/EX
2970 feet from S section line
2469 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30034
Operator: Zinke & Trumbo, Ltd.
Name & Address 1202 E. 33rd, Suite 100
Tulsa, OK 74105

Lease Name Merrill Well # 1-1
County Comanche 185.25
Well Total Depth 5700 feet
Conductor Pipe: Size 20" feet 80
Surface Casing: Size 8 5/8 feet 754

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X _____

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling License Number 5380

Address P.O. Box 12383, Wichita, KS 67277-2383

Company to plug at: Hour: 12:30 p.m. Day: 11 Month: 6 Year: 19 90

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 750'

1st plug at top of Arbuckle with 40 sx cement,

2nd plug at 780' with 50 sx cement, 3rd plug at 375' with 50 sx cement,

4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement,

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X _____

Operations Completed: Hour: 3 p.m. Day: 11 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 5580' with 50 sx cement,

2nd plug at 780' with 50 sx cement,

3rd plug at 375' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED 1990
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

DATE 6-25-90
INV. NO. 28473 6-13-90

Signed Stephen J. Pfeifer (TECHNICIAN)

EFFECTIVE DATE: 5-29-90

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas

033-20,784

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the X.C.C. five (5) days prior to commencing well

Expected Spud Date 5 25 90
month day year

SW SW NE Sec 1 Twp 34S S, Rg 16 East West

OPERATOR: License # 30034
Name: Zinke & Trumbo, Ltd.
Address: 1202 E. 33rd, Suite 100
City/State/Zip: Tulsa, OK 74105
Contact Person: Wayne Taylor
Phone: 918-743-5096

2970' feet from South line of Section
2469' feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5380
Name: Eagle Drilling

County: Comanche
Lease Name: Merrill Well #: 1-1
Field Name: unnamed

Well Drilled For: Well Class: Type Equipment:
X Oil Inj Infield X Mud Rotary
Gas Storage X Pool Ext. Air Rotary
OAWO Disposal Wildcat Cable
Seismic; # of Holes

Is this a Prorated Field? yes X no
Target Formation(s): Arbuckle test
Nearest lease or unit boundary: 330
Ground Surface Elevation: 1698 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 180'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 600-750
Length of Conductor pipe required: Not required
Projected Total Depth: 5700'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
... well ... farm pond X ... other

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #:
Will Cores Be Taken? yes X no
If yes, proposed zone:

Exp. 11/24/90

AFFIDAVIT

200' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101,

Pusher Butch Stiewer
SPUD DATE 5-31-90 INIT. MS
LENGTH SURFACE PLANNED 750
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE @ 754 CONDUCTOR 80'420
ANHYDRITE T. @ 250' B- ELEVATION
TD 5700' FORMATION Arbuckle
RAN PIPE @ 5580 DV TOOL ALT II DONE
Arbuckle Plug @ 174 Ft. W/ 50 SX Y N
Hag. / Council @ Ft. W/ SX
Base Surf. Pre. @ 780' Ft. W/ 50 SX
1/2 Base Anyh. @ 375' Ft. W/ 50 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ Ft. W/ SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W- 15 SX MOUSE HOLE W/ 10 SX
WATER WELL 1 SX (Irr. Well Pond
Hauling
TECHNICIAN S.P. DATE 6-8-90
TYPE OF CEMENT 60/40/6 gel
STARTING TIME 12:30 (AM/PM) DATE 6-11-90
COMPLETION TIME 3:00 (AM/PM) DATE 6-11-90
CEMENT COMPANY BS Titan

07-14-90