

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21176-00-00  
Spot: NESW Sec/Twnshp/Rge: 31-33S-19W  
1880 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: GIRK TRUST Well Number: 2  
County: COMANCHE Total Vertical Depth: 5830 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

Conductor Pipe Size: 20 feet: 40 GROUT ~~7189.48~~  
Production Casing Size: 4.5 feet: 5350 WITH 115 SX CMT  
Surface Casing Size: 8.625 feet: 650 WITH 330 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2003 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KEVIN WILES, SR. Company: AMERICAN WARRIOR Phone: (620) 272-4996

Proposed Plugging Method: PUMP 80 BBL ROTARY MUD. CHECK FL. PUMP 200 SX CMT & 1000# HULLS. RUN WIRE LINE & TAG CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/15/2003 1:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5284'. PERFS AT 5212-18'. 8 5/8" & 4 1/2" COLLAPSED AT 153'. 07/10/03: PUMP IN 80 BBL ROTARY MUD. ON VACUUM THROUGH OUT. FL AFTER JOB: APPROXIMATELY 20' FROM SURFACE. 07/14/03: PUMPED 200 SX CMT & 1000# HULLS. NO PRESSURE. ON SLIGHT VACUUM AFTER JOB. 07/15/03: RAN WIRE LINE. TAG CMT @ 57' FROM SURFACE. FILLED TO SURFACE WITH 20 SX CMT.

RECEIVED  
7-18-03  
JUL 18 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 3% CC BY ALLIED. RECOVERED 153' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
JUL 15 2003  
KCC Dodge City

Signed: \_\_\_\_\_

(TECHNICIAN)  
INVOICED  
DATE 7-18-03  
WV. NO. 2004060081

Form CP-243