

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20069-00-00
Spot: SESWNW Sec/Twnshp/Rge: 13-2S-14E
2310 feet from N Section Line, 990 feet from W Section Line
Lease Name: PYLE Well #: 4-83
County: NEMAHA Total Vertical Depth: 3563 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3550		200 SX
SURF	8.625	250		340 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2014 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION, INC. Phone: (785) 483-1559

Proposed Plugging Method: PER KCC INSTRUCTION

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 03/20/2014 2:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

PERFORATED THE PRODUCTION CASING AT 1400' AND 300'. RAN TUBING DOWN TO 2400' AND PUMPED 50 SACKS OF CEMENT. PULLED THE TUBING UP TO 1400' AND PUMPED 50 SACKS OF CEMENT. PULLED THE TUBING OUT. HOOKED ON TO THE PRODUCTION CASING AND CIRCULATED 78 SACKS OF CEMENT TO THE SURFACE INSIDE AND OUTSIDE OF THE PRODUCTION CASING.

Top	Bot	Thru	Comments
3472	3476		

RECEIVED
MAY 15 2014
KCC Chanute Dist. #3
TH

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman
(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

MAY 19 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3