

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20076-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 13-2S-14E
990 feet from N Section Line, 330 feet from W Section Line
Lease Name: PYLE Well #: 5-83
County: NEMAHA Total Vertical Depth: 3560 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2960		
PROD	5.5	3555		175 SX
SURF	8.625	240		187 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2014 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION, INC. Phone: (785) 483-1559

Proposed Plugging Method: PER KCC INSTRUCTIONS

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 03/21/2014 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

PERFORATED THE PRODUCTION CASING AT 1400' AND 300'. RAN TUBING DOWN TO 2800' AND PUMPED 50 SACKS OF CEMENT. PULLED THE TUBING UP TO 1400' AND PUMPED 50 SACKS OF CEMENT. PULLED THE TUBING OUT. HOOKED ON TO THE PRODUCTION CASING AND SQUEEZED 78 SACKS OF CEMENT TO THE SURFACE ON THE INSIDE AND OUTSIDE OF THE PRODUCTION CASING.

Perfs:

Top	Bot	Thru	Comments
3504	3507		
2839	2843		

RECEIVED
MAY 21 2014
KCC Chanute Dist. #3
TH

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman
6/04/14 (TECHNICIAN)

KCC WICHITA
MAY 23 2014
RECEIVED