

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21277-00-00
Spot: NWNESENE Sec/Twnshp/Rge: 7-12S-17W
3722 feet from S Section Line, 432 feet from E Section Line
Lease Name: HERMAN Well #: 2
County: ELLIS Total Vertical Depth: 3686 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3657		100 SX
SURF	8.625	254		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2014 12:15 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DAVE HEIN Company: GRADY BOLDING CORP Phone: (620) 565-2240

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 7 sx gel and 500 # hulls.
PC at 1385' w/375 sx cement.
Arb - 3657' - 3658'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2014 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to 8 5/8" casing and pumped 25 sx cement w/200 psi and 200 psi shut in pressure.
Rigged to 4 1/2" casing and pumped 50 sx cement w/200 # hulls mixed in followed by 7 sx gel followed by 85 sx cement w/300 # hulls mixed in. Pressured casing to 1000 psi and 800 psi shut in pressure.
Topped with 25 sx cement.

GPS: 39.02640 -099.24297
3719' FSL 355' FEL
NW NE SE NE

Perfs:


Remarks: QUALITY CEMENTING CO TICKET # 7185

Plugged through: CSG

KCC WICHITA
MAY 09 2014
RECEIVED

District: 04

Signed


(TECHNICIAN)

(TECHNICIAN)

CM