

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-00612-00-00  
Spot: SESESWNW Sec/Twnshp/Rge: 19-12S-17W  
2929 feet from S Section Line, 4233 feet from E Section Line  
Lease Name: KRANNAWITTER Well #: 1  
County: ELLIS Total Vertical Depth: 3688 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: 114 NORTH MAIN P.O. BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3674		175 SX
SURF	8.625	189		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2014 8:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: DAVE HEIN Company: GRADY BOLDING CORP Phone: (785) 623-2084

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Tubing parted in well around 1400'. Rods parted 25' above tubing. Worked on removing for 2 days. Rods cork screwed.  
Couldn't get on them.  
Arb-3672' - 3688'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/26/2014 12:00 AM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Perf Tech perforated at 800' and 200'.  
Professional pulling ran in hole with tubing to 1044'. Quality rigged to tubing and pumped 95 sx cement to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 260 sx cement w/300 # hulls mixed in to pressure with 500 psi and 200 psi shut in pressure. Rigged to 8 5/8" casing and pumped 5 sx cement to pressure with 100 psi and 100 psi shut in pressure.  
Topped with 30 sx cement.

GPS: 38.99529 -099.25688  
3001' FSL 4170' FEL  
NE SE SW NW

Perfs:

Remarks: QUALITY OILWELL CEMENTING TICKET # 7184

Plugged through: TBG

KCC WICHITA

MAY 09 2014

RECEIVED

District: 04

Signed [Signature]  
(TECHNICIAN)

CM