

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24935-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 20-19S-14W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: LEROY B Well #: 1
County: BARTON Total Vertical Depth: 3634 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3629	2400	125 SX
SURF	8.625	827		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2014 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORP. Phone: (620) 564-2240

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement.
Cut casing at 2400'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 850' and pumped 60 sx cement w/100 # hulls. Pulled casing to 400'. Circulated cement to surface with 100 sx cement and 150 # hulls. Pulled casing and hole stayed full.

GPS: 38.37711 -098.90250

Perfs:

Top	Bot	Thru	Comments
3550	3554		

KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING

MAY 09 2014

Plugged through: CSG

RECEIVED

District: 04

Signed Bruce Rodie
(TECHNICIAN)

6/04/14

CM

APR 25 2014

Form CP-2/3