

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02414-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 17-12S-17W
4924 feet from S Section Line, 4332 feet from E Section Line
Lease Name: SCHMEIDLER A Well #: 5
County: ELLIS Total Vertical Depth: 3762 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3762		125 SX
SURF	8.625	190		375 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2014 12:30 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DAVE HEIN Company: GRADY BOLDING CORP. Phone: (785) 623-2084

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.
Well was perforated in 1954 at 1375' w/500 sx cement.
No casing leaks or high fluid.
Perforations: 3737' - 3739'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/22/2014 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality rigged to 5 1/2" casing and pumped 50 sx cement w/200 # hulls mixed in followed by 14 sx gel followed by 200 sx cement w/200 # hulls. Pumped to pressure with 400 psi and 150 psi shut in pressure. Rigged to 8 5/8" surface casing and pumped 5 sx cement to pressure w/400 psi and 400 psi shut in pressure.

GPS: 39.01527 -099.23840
4948' FSL 4276' FEL
SW NE NW NW

Perfs:

Top	Bot	Thru	Comments
3737	3739		

KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING TICKET # 416

MAY 09 2014
RECEIVED

Plugged through: CSG

District: 04

Signed _____

[Signature]
6/04/14
(TECHNICIAN)

CM

APR 29 2014