

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20157-00-00
Spot: NESWNE Sec/Twnshp/Rge: 26-23S-40W
2794 feet from S Section Line, 1652 feet from E Section Line
Lease Name: SHETTERLY Well #: 1-26
County: HAMILTON Total Vertical Depth: 2520 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2520		500 SX
SURF	8.625	325		250 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/30/2014 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 100 SX CMT & 200# HULLS. DISPLACE TO 100'. RUN LOG FROM 1000' TO DETERMINE TOC. PERFORATE AND OR RUN TBG AS REQUIRED. 50 SX CMT FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT & 200# HULLS. DISPLACE WITH WATER TO 1000'. PRESSURE TO 700#. HOLDING. RUN CBL FROM 1000' TO 40'. TOC @ 90'. RUN TBG TO 908' & CIRCULATE CMT TO SURFACE WITH 60 SX CMT. TOP OFF WITH 5 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 400#.

Perfs:

Top	Bot	Thru	Comments
2448	2458		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
6/03/14

(TECHNICIAN)

RECEIVED

MAY - 5 2014

KCC DODGE CITY

KCC WICHITA

MAY 12 2014

RECEIVED

Form CP-2/3

NOT