

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20509-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 19-21S-40W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease Name: WELTON Well #: 2-19
County: HAMILTON Total Vertical Depth: 2820 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2819	0	WITH 650 SX CMT
SURF	8.625	337		WITH 170 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/06/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 100 SX CMT & 250# HULLS. DISPLACE TO 1100'. TEST CASING TO 700#. RUN CBL TO DETERMINE TOC. RUN TBG AND/OR PERFORATE AT REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT & 250# HULLS DOWN CASING. DISPLACE WITH WATER TO 1450'. RUN CBL FROM 1220' TO 50'. FOUND TOC @ 660'. RUN TBG TO 1200'. SPOT 60 SX CMT FROM 1200' TO 500'. PERFORATE 4 HOLES AT 350'. ESTABLISH INJECTION RATE 1 1/2 BPM AT 275 PSI. CIRCULATE CMT TO SURFACE USING 85 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2770	2786		

KCC WICHITA
MAY 20 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
6/03/14
(TECHNICIAN)

RECEIVED

MAY - 9 2014

KCC DODGE CITY