

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21086-00-01  
Spot: NWNWNE Sec/Twnshp/Rge: 7-22S-34W  
4928 feet from S Section Line, 2318 feet from E Section Line  
Lease Name: WHEAT Well #: 2-7  
County: FINNEY Total Vertical Depth: 2885 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6200 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2830	0	WITH 650 SX CMT
SURF	8.625	1796		WITH 600 SX CMT

Well Type: HI UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/07/2014 12:30 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 100 SX CMT WITH 300# HULLS. DISPLACE TO 1000'. TESTING TO 700#. RAN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS NECESSARY.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/07/2014 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 300# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1000'. TEST CASING TO 700#. RUN CBL FROM 1000' TO 150'. TOC @ 350'. RUN TBG TO 1200'. SPOT 45 SX CMT FROM 1200' TO 300'. TOOH W/TBG. PERFORATE 4 HOLES AT 300'. CIRCULATE CMT TO SURFACE USING 70 SX CMT, LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2586	2650		

KCC WICHITA  
MAY 20 2014  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Ken Jehlik (TECHNICIAN)  
6/03/14

RECEIVED

MAY 13 2014

KCC DODGE CITY