

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40245-00-00
Spot: NWNWNSW Sec/Twnshp/Rge: 3-34S-11E
2477 feet from S Section Line, 3839 feet from E Section Line
Lease Name: DJ MOORE Well #: 3
County: CHAUTAUQUA Total Vertical Depth: 1111 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	820		0 SX
SURF	10	42		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Spot 50' plug of cement on bottom. Perforate at 700' and 350'. Spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 04/24/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1/2" to 1100' gelled hole and spotted 65 sacks of cement in shot hole. Pulled 1/2" and perforated casing at 800', 600' and 350'. Ran 1" back into 800' and spotted 20 sack plug. Pulled up to 600' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface inside and outside casing. Pulled 1" and topped well off. A total of 220 sacks of cement were used to plug this well.

Perfs:

RECEIVED
MAY 13 2014
KCC Chanute Dist. #3
DS

Remarks: ABANDONED WELL PLUGGED TO MEET COMPLAINEE.

Plugged through: TBG

District: 03

Signed [Signature]
[Signature] (TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

MAY 19 2014
CONSERVATION DIVISION
WICHITA, KS