

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40318-00-00

Spot: NESWSENE

Sec/Twnshp/Rge: 36-34S-11E

3097 feet from S Section Line, 758 feet from E Section Line

Lease Name: DUNHAM-LEMMON

Well #: 59

County: CHAUTAUQUA

Total Vertical Depth: 1167 feet

Operator License No.: 32255

Op Name: KANSAS ENERGY COMPANY, L.L.C.

Address: BOX 68

SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4	1149		0 SX
SURF	10	16		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/02/2014 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: P.J. BUCK

Company:

Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/03/2014 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to TD gelled hole and spotted 10 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran back into 700' and spotted 10 sack plug. Pulled up to 350' and circulated cement to surface inside and outside casing. Pulled 1" and topped well off. A total of 158 sacks of cement were used to plug this well.

RECEIVED

APR 22 2014

KCC Chanute Dist. #3

DS

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
4/24/14

(TECHNICIAN)

KCC WICHITA

APR 28 2014

RECEIVED

Form CP-2/3