

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-00730-00-00  
Spot: NWNESESW Sec/Twnshp/Rge: 6-23S-3W  
1254 feet from S Section Line, 2178 feet from W Section Line  
Lease Name: FREDERICK Well #: 4  
County: HARVEY Total Vertical Depth: 3379 feet

Operator License No.: 7116  
Op Name: KANTOR OIL COMPANY, LLC  
Address: 15 W 6TH ST STE 2601  
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3352		150 SX
SURF	8.625	280		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2014 12:00 AM  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: LARRY RESSLER Company: G & L WELL SERVICE Phone: (620) 664-0597

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/21/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

TUBING & PACKER STUCK AT 3300'. PUMPED 25 SXS CEMENT THROUGH TUBING, WAITED 2 HOURS, PRESSURE UP TO 500 LBS. SHOT TUBING OFF AT 2950', PUMPED 20 SXS OF CEMENT, TAGGED & 2800'. SHOT CASING @ 623' PUMPED 35 SXS CEMENT THRU 620' OF TUBING, TAGGED @ 429'. SHOT 4 SHOTS @ 340' RAN IN WITH TUBING TO 340' & CIRCUALTED TO SURFACE WITH 160 SXS CEMENT. CUT WINDOWS IN SURFACE PIPE, CEMENT @ TOP OF CASING.

Perfs:

Top	Bot	Thru	Comments
3352	3379		

**KCC WICHITA**  
**MAY 06 2014**  
**RECEIVED**

Remarks: COPELAND CEMENTING OUT OF BURTON, CLASS A CEMENT, TICKET #40827; JUNK IN HOLE

Plugged through: TBG

District: 02

Signed B. J. Hope  
6/04/14 (TECHNICIAN)