

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20007-00-01
Spot: S2SWNWNW Sec/Twnshp/Rge: 13-2S-14E
1240 feet from N Section Line, 330 feet from W Section Line
Lease Name: PYLE Well #: 7-83
County: NEMAHA Total Vertical Depth: 3535 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3533		260 SX
SURF	8.625	185		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2014 2:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION, INC. Phone: (785) 483-1559

Proposed
Plugging
Method:

PER KCC INSTRUCTIONS

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 03/20/2014 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

PERFORATED THE PRODUCTION CASING AT 1900', 1400', AND 300'. RAN TUBING DOWN TO 1900' AND 50 SACKS OF CEMENT. PULLED THE TUBING UP TO 1400' AND PUMPED 50 SACKS OF CEMENT. PULLED THE TUBING OUT. HOOKED ON TO THE PRODUCTION CASING AND CIRCULATED 134 SACKS OF CEMENT TO THE SURFACE INSIDE AND OUTSIDE OF THE PRODUCTION CASING.

Perfs:

Top	Bot	Thru	Comments
3490	3492		
3472	3476		

RECEIVED
MAY 15 2014
KCC Chanute Dist. #3
TH

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

6/04/14

MAY 19 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3