

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-19010-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 13-2S-14E
1650 feet from N Section Line, 330 feet from W Section Line
Lease Name: PYLE Well #: 8-83
County: NEMAHA Total Vertical Depth: 3930 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 3745 | | 300 SX |
| SURF | 8.625 | 180 | | 100 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2014 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION, INC. Phone: (785) 483-1559

Proposed Plugging Method: PER KCC INSTRUCTIONS

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 03/21/2014 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

PERFORATED THE CASING AT 1400' AND 300'. RAN TUBING DOWN TO 2400' INSIDE THE PRODUCTION CASING AND PUMPED 50 SACKS OF CEMENT. PULLED THE TUBING UP TO 1400' AND PUMPED 50 SACKS OF CEMENT. PULLED THE TUBING OUT. HOOKED ON TO THE PRODUCTION CASING AND PUMPED 75 SACKS OF CEMENT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3498 | 3500 | | |
| 3476 | 3480 | | |

RECEIVED
MAY 01 2014
KCC Chanute Dist. #3
TH

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman
6/04/14

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

MAY 05 2014

RECEIVED