

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 27 1967

11-27-67

CONSERVATION DIV  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed November 13, 1967.

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co., Inc has this  
date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Company, Inc.

Complete Address: 1434 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: Jackson Well No. # 1

Location: SW NE Sec. 22 Twp. 34 Rge. 17 (E) (W) W

County Comanche Total Depth 5280' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

442' of 8 5/8" surface pipe, cement circulated with 325' sacks. Fill  
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent