

State of Kansas



15-033-20348-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

MAY 30 1980
5-30-80
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Cahn of Lear Pet. has this date requested permission to plug the following described well:

Mr. Cahn guarantees payment of the plugging fee.

Operator's full Name: Lear Pet., Exploration, Inc.

Complete Address: 2601 NW Expressway, 2601 Oil Ctr., Bldg. Ok. City, Ok

Lease Name: Brass Well No. 1-2

Location: C NW NW Sec. 2 Twp. 34s Rge. 19(E)(W) W

County: Comanche Total Depth 6573 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Cahn was instructed to plug the well as follows:

292' 8 5/8" casing. Set 50 sax cement plug at 700'-Set 40
sax cement plug at 300'-Bridge at 40' & 10 sax cement to 5'
below Gl. 5 sax in rat hole. Cemented by Howco.

Very truly yours,

Conservation Division Agent