



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Sunny Johnson of Lillard Casing Pullers Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Union Oil Co. of California

Complete Address: 2000 Classen Center South Building Oklahoma City Okla 73106

Lease Name: Hazel Beals

Well No. 1

Location: C-NE-SW

Sec. 5 Twp. 34S Rge. 17W (E) (W)

County: Comanche

Total Depth: 5940'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Johnson was instructed to plug the well as follows:

There is 246' of 13 3/8" conductor pipe + 2592' of 8 5/8" surface casing cement circulated. The Perforations were at 4393' to 4576'. Plug back was at 4830'. 1st plug pumped 1 bbl. hull + 35 lbs. of cement to bottom of hole. 2nd plug at 2642' with 50 lbs. of cement. 3rd plug 40' to 0' with 10 lbs. of cement. Plugging accomplished by Lillard casing Pullers Inc. They recovered 3510' of production pipe. There was 5799' of 5 1/2" production pipe cemented, cement was 4000' out side of pipe.

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1982
1-26-82
CONSERVATION DIVISION
Wichita Kansas

Paul Luther
Conservation Division Agent