



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 8 1963

2-8-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: L. B. Jackson Drilling Co.

Complete Address: 503 Mayo Bldg., Tulsa, Oklahoma

Lease Name: Petro Well No. # 1

Location: G SE NW NW Sec. 7 Twp. 34 Rge. 19 (E) (W) W

County Comanche Total Depth 6313 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Deacon was instructed to plug the well as follows:

5654' of 5 1/2" long string. Plugged back to 5245'. Top of perforation 5200'. Sanded to 5180' and cemented with 5 sacks.

369' of 8 5/8" surface pipe circulated with cement. Fill hole with mud to 200', 10' rock bridge cemented with 20 sacks.

Fill hole to 40' with mud, 10' rock bridge with 10 sacks cement to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent