



15-033-30004-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1965
8-17-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bob Burris of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Brooks Hall

Complete Address: 1710 Liberty Bank Bldg., Oklahoma City, Okla.

Lease Name: Oller Unit Well No. # 1

Location: C NE NE Sec. 12 Twp. 34 Rge. 19 (E) (W) W

County Comanche Total Depth 6339' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

470' of 8 5/8" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat and mouse
holes with 4 sacks.

Very truly yours,

Archie Elving