

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-03246-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 10-10S-25W  
2310 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: ELRICK UNIT Well #: 6-1  
County: GRAHAM Total Vertical Depth: 4020 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4019		100 SX
SURF	8.625	163		115 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2014 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: \_\_\_\_\_ Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-9405

Proposed Plugging Method: Shot perforations at 157', 1265', 2155' and 2650'  
Perforations at 3776' - 3993'  
CIBP at 3725'  
Ordered 525 sx 60/40 pozmix 4% gel cement w/700 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/18/2014 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3695' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 3095' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2245' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1395' and pumped 145 sx cement. Good circulation of cement. Tied on to back side and squeezed with 55 sx cement. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3776	3993		

KCC WICHITA  
JUN 30 2014  
RECEIVED

Remarks: ALLIED CEMENTING TICKET # 63458

Plugged through: TBG

District: 04

Signed

7/1/14 CKM

(TECHNICIAN)

CM

JUN 24 2014