

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22252-00-01
Spot: NESWSE Sec/Twnshp/Rge: 4-30S-13W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: LAMBERT OWWO Well #: 1-4
County: BARBER Total Vertical Depth: 4720 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	10.75	265		WITH 235 SX CMT
PROD	4.5	4718	2580	WITH 225 SX CMT
SURF	8.625	1004		WITH 230 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2014 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 50 SX CMT. PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 06/20/2014 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 150# HULLS WITH 40 SX CMT. PRESSURED TO 500#. 1ST PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4493	4503		
4492			
4485	4489		
4383	4404		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG


KCC WICHITA

JUN 27 2014

RECEIVED

District: 01

Signed


7/1/14 ccm (TECHNICIAN)

RECEIVED
JUN 25 2014
KCC DODGE CITY

Form CP-2/3