

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21112-00-00  
Spot: NESE Sec/Twnshp/Rge: 32-29S-13W  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: PALMQUIST Well #: 2  
County: PRATT Total Vertical Depth: 4790 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4785	2380	WITH 275 SX CMT
SURF	10.75	250		WITH 275 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2014 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 100# HULLS WITH 30 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 06/24/2014 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 150# HULLS WITH 30 SX CMT. PRESSURED TO 500#. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4502	4524		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA  
JUN 27 2014  
RECEIVED

District: 01

Signed [Signature]  
7/1/14 CKM (TECHNICIAN)

RECEIVED  
JUN 25 2014  
KCC DODGE CITY

[Signature]