

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20610-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 13-28S-16W
335 feet from S Section Line, 3043 feet from E Section Line
Lease Name: LONG Well #: 1
County: KIOWA Total Vertical Depth: 4435 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4620		WITH 2 SX CMT
PROD	4.5	4729	2326	WITH 150 SX CMT
SURF	8.625	435		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/24/2014 2:00 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: CIBP @ 4620' WITH 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS Witness Type: NONE
Date/Time Plugging Completed: 06/24/2014 4:00 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

SET CIBP @ 4620' WITH 2 SX CMT. CUT CASING AT 2710' DID NOT WORK. CUT CASING AT 2326'. 1ST PLUG AT 1114' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 509' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4667	4674		

KCC WICHITA
JUN 27 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed

Daniel Sellers
7/1/14 CSM (TECHNICIAN)

RECEIVED
JUN 25 2014
KCC DODGE CITY