

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23535-00-00  
Spot: NENESWSW Sec/Twnshp/Rge: 1-13S-18W  
999 feet from S Section Line, 4086 feet from E Section Line  
Lease Name: CRISSMAN Well #: 1  
County: ELLIS Total Vertical Depth: 3674 feet

Operator License No.: 5386  
Op Name: PRODUCTION DRILLING, INC.  
Address: 1023 RESERVATION RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3670		300 SX
SURF	8.625	220		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2014 10:00 AM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: JUSTIN TROUT Company: PRODUCTION DRILLING Phone: (785) 625-1189

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Perforations: 3624' - 3644'.  
Tubing stuck in hole at 1776'.  
Rods stuck at 1850'. Casing parted.  
Had 300 sx cement pumped down backside.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/18/2014 12:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Gemni Wireline perforated at 1750', 1340' and 700'.  
Western Well Service ran in hole with tubing to 1722'. Quality rigged to tubing and mixed and pumped 100 sx cement. Pulled tubing to 713'. Quality rigged to tubing and mixed and pumped 85sx cement w/250 # hulls mixed in to circulate cement up 5 1/2" casing. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 20 sx cement to pressure with 300 psi and 200 psi shut in pressure. Rigged to 8 5/8" casing and pumped 5 sx cement with instant pressure.

GPS: 38.94622 -099.27510  
SE NE SW SW  
979' FSL 3984' FEL

Perfs:


Top	Bot	Thru	Comments
3624	3644		

Remarks: QUALITY OILWELL CEMENTING TICKET # 247

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

7/1/14 CKM

KCC WICHITA

JUN 30 2014

RECEIVED

JUN 24 2014