

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-22205-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 31-15S-30W  
1015 feet from N Section Line, 431 feet from W Section Line  
Lease Name: YORK 31AB Well #: 1  
County: GOVE Total Vertical Depth: 4600 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		175 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2014 12:00 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: KERBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 06/22/2014 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st plug @2215 w/50 sx  
2nd plug @1190 w/100 sx  
3rd plug @270 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

KCC WICHITA  
JUN 30 2014  
RECEIVED

District: 04

Signed Richard Williams  
71114 CKM (TECHNICIAN)

CM