

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
REV. 6-4-68  
RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1978  
3-13-78  
CONSERVATION DIVISION  
Wichita, Kansas

R

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 033 - 30000 - 0000 (of this well)

Operator's Full Name J. M. Huber Corp.  
Complete Address 3450 - Liberty Tower, Okla. City, Okla. 73102  
Lease Name Eissel Bidelle Well No. 2  
Location W/2 - NW - Sec. 12 Twp. 23 Rge. 17 (E) (W) X  
County Comanche Total Depth 5800

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Lillard Casing Pulling Inc.

Address Box 963 Woodward, Okla. 73801 License No. 618

Operation Completed: Hour 1:15 pm Day 10 Month March Year 1978

The above well was plugged as follows:

405' - 8 5/8" casing w/ 350 sack cement - 4 1/2" casing set @ 5199' w/ 215  
sack cement - top plug @ 5086' - Lillard Casing Pulling mixed & pumped  
35 sack cement - release plug & pumped plug to 4990' w/ heavy mud -  
pulled pipe to 455' - pumped 70 bbl. heavy mud in hole - fluid  
level the same - mixed & pumped 35 sack cement - fluid level same  
found bridge @ 996' - fluid @ 447' - build bridges w/ wood & dirt @  
447' - dump 9 yards Ready Mix Cement to bottom of cellar -  
build bridge w/ Ready Mix - Greensburg, Ia. 67054 - 4200' 4 1/2" casing

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 3-14-78  
INV. NO. 6916-W