

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20, 510-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name GOULD OIL COMPANY

Complete Address 260 N. ROCK ROAD, SUITE 210, WICHITA, KS 67206

Lease Name CARLISLE Well No. 1

Location C. SE. SW Sec. 34 Twp. 33 Rge. 17 (East)(West)

County COMANCHE Total Depth 5950'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor H & H Casing Pulling

Address 408 Circle Dr., Box 563, BURETON, KS 67020 License No. _____

Operation Completed: Hour: 9:30AM Day: 18 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The 8 5/8" s.p. set @ 751' w/450 sy. Common & 4 1/2" tube set @ 5335' w/200 sy., 3510' of 4 1/2" recovered. The following sequence was used for plugging the well: 3 sy hulls followed by 10 sy gel then 70 sy 50-50 Poz-mix w/4% gel-3% C.C. mixed. Pumped 10 sy gel then 1/2 sy hulls followed by 8 5/8" rubber & wood plug and 80 sy. Cement.

Cementing done by Sun Oilwell Cement

Amount of Surface Casing: 751'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: R. Barlett
Conservation Division Agent
order by S. Durrant

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1982
8-24-82
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 8-31-82

INV. NO. 989-w